



LHC: Status and Outlook





Sergio Bertolucci CERN, Geneva Madrid, March 10, 2010





Major LHC challenges



High design Centre-of-mass energy of 14 TeV in given (ex LEP) tunnel

- •Magnetic field of 8.33 T with superconducting magnets
- •Helium cooling at 1.9 K
- •Large amount of energy stored in magnets
- •"Two accelerators" in one tunnel with opposite magnetic dipole field and ambitious beam parameters pushed for very high of luminosity of $10^{34}\,\mathrm{cm^{-2}\,s^{-1}}$
- •Many bunches with large amount of energy stored in beams

Complexity and Reliability

•Unprecedented complexity with 10000 magnets powered in 1700 electrical circuits, complex active and passive protection systems,

- Emittance conservation $\varepsilon_N = \beta \gamma \varepsilon$, related to phase space density conservation, Liouville constant "intrinsic" normalized emittance ε_N , real space emittance ε decreases with energy
- in absence of major energy exchange in synchrotron radiation / rf damping
- clean, perfectly matched injection, ramp, squeeze, minimize any blow up from: rf,
- kicking beam, frequent orbit changes, vibration, feedback, noise,...
- dynamic effects persistent current decay and snapback
- non-linear fields (resonances, diffusion, dynamic aperture, non-linear dynamics)



Beam parameters, LHC compared to LEP



	LHC	LEP2
Momentum at collision, TeV/c	7	0.1
Nominal design Luminosity, cm ⁻² s ⁻¹	1.0E+34	1.0E+32
Dipole field at top energy, T	8.33	0.11
Number of bunches, each beam	2808	4
Particles / bunch	1.15E+11	4.20E+11
Typical beam size in ring, µm	200 - 300	1800/140 (H/V)
Beam size at IP, µm	16	200/3 (H/V)

■ Energy stored in the magnet system: 10 GJoule Airbus A380, 560 t at 700 km/h

Energy stored in one (of 8) dipole circuits:(sector)

■ Energy stored in one beam: 362 MJ 20 t plane

■ Energy to heat and melt one kg of copper: 0.7 MJ


the LEP2 total stored beam energy was about 0.03 MJ



The total stored energy of the LHC beams



Nominal LHC design: 3.2×10^{14} protons accelerated to 7 TeV circulating at 11 kHz in a SC ring



LHC: > 100 × higher stored energy and small beam size: ~ 3 orders of magnitude in energy density and damage potential. Active protection (beam loss monitors, interlocks) and collimation for machine and experiments essential. Only the specially designed beam dump can safely absorb this energy.




Damage potential: confirmed in controlled SPS experiment




controlled experiment with beam extracted from SPS at 450 GeV in a single turn, with perpendicular impact on Cu + stainless steel target

450 GeV protons

r.m.s. beam sizes $\sigma_{x/y} \approx 1 \text{ mm}$





SPS results confirmed:

 8×10^{12} clear damage 2×10^{12} below damage limit

for details see V. Kain et al., PAC 2005 RPPE018

For comparison, the LHC nominal at 7 TeV: $2808 \times 1.15 \times 10^{11} = 3.2 \times 10^{14} \text{ p/beam}$


at
$$< \sigma_{x/y} > \approx 0.2 \text{ mm}$$

over 3 orders of magnitude above damage level for perpendicular impact



The CERN accelerator complex: injectors and transfer





simple rational fractions for synchronization on a single frequency

tor at injection

Beam size of protons decreases with energy : area $\sigma^2 \propto 1/E$

Beam-size langest at injection, using the full aperture



Critical Issues

Past

- •QRL cryo-line (He supply)
- •DFB power connections, warm to cold transition
- •Triplet quadrupoles differential pressure

More recent

- •PIM plug in module with bellow, systematically checked / repaired after warm up using "ping-pong" ball with RF-emitter: polycarbonate shell, ∅ 34 mm, 15 g, 2h battery powered, 40 MHz emitter, signals recorded by LHC BPM
- •Vacuum leaks, condensation humidity sector 3/4
- Magnet powering check / correct : min/max, cabling polarity
- •Single event upset, radiation to electronics, shielding etc
- •Magnet re-training magnets quenching below what was reached in SM18





10 September 2008






10:30 beam 1 3 turns

15:00 beam 2 3 turns

22:00 beam 2 several 100 turns




few days later...







September 19, 2008: incident in sector 3-4



Upper Copper Profile

Upper Tin/Silver Soldering alloy Layer

Lower Tin/Silver Soldering Alloy Layer

Lower Copper U Profile

Cable Junction Box Cross-sectior

The incident was traced to a faulty electrical connection between segments of the LHC's superconducting cable (busbars)

High impact was caused by collateral damage





2 most severely damaged interconnects


53 Magnets (along a zone of about 700 m) to be removed from tunnel and repaired/exchanged (a few % of entire LHC)






Busbar Splice





Electrical arc between C24 and Q24




V lines









QQBI.27R3 M3 line



Bringing back the LHC: how was it done?


Five Phases:

- 1.Repair of sector 34
- 2. Consolidation and Avoidance of collateral damage
- 3. Hardware Commissioning
- 4. Preparations for Beams (long term)
- 5. Operation with Beams

Phase 1 and 2 Repair and Consolidation

Phase 1 +2

The LHC repairs in detail



sector 3-4 : Magnet repair in SMI2




Last Repaired Magnet (SSS) going down (30/4/2009)




Magnet protection and anchoring


















Show sample






Busbar Splice



normal conducting, soldered electrical connection between SC cables

1684 units \times 6 \approx 10 000 splices at magnet interconnects; 1/3 dipole, 2/3 quads



possible problems in soldering:

A. Siemko et al. LMC 5/08/09

overheating - SnAg loss

too cold - SnAg unmelted, poor connection


Now possible to diagnose: X-ray, ultrasound, resistance measurement.

Most reliable: resistance measured at room temperature

good: 10 μ Ω dipole (RB), 17 μ Ω quadrupole (RQ).

Measured in 5 sectors which were warmed up. Fixed all above ~ 40 μ Ω . Other sectors measured at 80 K

RB: case 1 (instantaneous quench in busbar/magnet)




Thermal propagation time (for case 2)

Experience from HWC for RB quenches at 7-11 kA.


Assume that the joint quenches after half the MB-MB thermal propagation time,

so
$$t_{JQ}$$
=0.5*(70- I_{Q} /300)

Maybe possible to get more accurate value from thermal analysis.....



RB: case 2 (quench propagation from magnet to busbar)



Enhanced QPS

Role of the Enhanced QPS System

- To protect against the new 'problems' discovered in 2008
 - The Aperture-Symmetric Quench feature in the Main Dipoles and
 - Defective Joints in the Main Bus-bars, inside or inbetween the magnets.

QPS Upgrade also allows

- precision measurements of the joint resistances at cold (sub-n Ω range) of every Busbar segment. This will allow complete mapping of the splice resistances (the bonding between the s.c. cables).
- To be used as the basic monitoring system for future determination of busbar resistances at warm (min. 80 K), to measure regularly the continuity of the copper stabilizers.



The nQPS project

DQQTE board for ground voltage detection

(total 1308 boards, 3 units/crate)

DQLPUS Power Packs
2 units / rack (total 872 units)

DQLPU-type S crate total 436 units



DQAMG-type S controller board 1 unit / crate, total 436 units



DQQBS board for busbar splice detection 5 such boards / crate, total 2180 units



DQQDS board for SymQ detection

4 boards / crate, total 1744

Original racks




'Internal' and 'external' **cables** for sensing, trigger, interlock, UPS power, uFIP (10'400 + 4'400)






2 UPS Patch Panels / rack & 1 Trigger Patch Panel / rack total 3456 panel boxes


Pyramid for Splice Mapping




Splice Mapping of Dipoles

QPS team







LHC: a spectacular comeback! Friday November 20

18:30 Beam 1


- 19.00 beam through CMS (23, 34, 45)
 - beam1 through to IP6 19.55 Starting again injection of Beam1
 - corrected beam to IP6, 7, 8, 1
 2h10 for 27km: 12.5km/h average speed
- 20.40 Beam 1 makes 2 turns
 - Working on tune measurement, orbit, dump and RF
 - Beam makes several hundred turns (not captured)
 - Integers 64 59, fractional around .3 (Qv trimmed up .1)
- 20.50 Beam 1 on beam dump at point 6
- 21.50 Beam 1 captured

22:15 Beam2

- 23.10 Start threading Beam2
 - Round to 7 6 5 2 1

1h25 for 27km: a bit faster

- 23.40 First Turn Beam2
 - Working on tune measurement, orbit, dump and RF
 - Beam makes several hundred turns (not captured)
 - Integers 64 59, fractional around .3 (Qv trimmed up .05)
- 24.10 Beam 2 captured




Beam threading

Threading by sector:

- One beam at the time
- □Beam through 1 sector (1/8 ring), correct trajectory, open collimator and move on.

Beam 2 threading



Beam Status

POINT 6

POINT 7

Betatron

Cleaning

POINT 4


POINT 2


POINT 3

Momentum

Cleaning

Friday: 8:15pm: Beam 1 First 2 turns







Beam is circulating and stable

- magnets
- power supplies
- vacuum
- RF
- cryogenics
- all infrastructure
- optics
- injection


BCT – lifetime around 10h




Dispersion B1




Green dots are measured: blue line calculated




Tune measure and trim



BCT – lifetime around 10h



Dispersion B1




Green dots are measured: blue line calculated


Monday afternoon

- Both beams circulating in LHC. Hands off by OP for half an hour.
- Transverse Steering into collision using BPMs through 1 and 5.
- Hands off by OP for half an hour
- Recorded collision events in ATLAS and CMS
- From 16:00
 - Two beams in LHC at buckets 1 and 8911
 - Quiet beams for ALICE
 - Then 2 beams in LHC at buckets 1 and 26701
 - Quiet beams for LHCb
- Recorded collision events in ALICE and LHCb
- From 19.00
 - Beam 2 back in bucket 1
 - 2 beams in for collimation set up
 - Quickly steer IR5 (with new knob) and IR1
 - Quiet beams for 15' for CMS and ATLAS


ALICE



ATLAS




CMS



LHCb

LHCb Event Display



Monday November 30

Both beams accelerated at 1.18 TeV!



LHC experiments: a spectacular start as well!


- Experiments showing their readiness
- Excellent experiment-machine interface
- Very encouraging news from the side of the backgrounds.
- Fast data turnaround times





Event Displays








More Event Displays..











events

Vertex reconstruction








3 ways of reconstruction the vertex: Pixels only; all ITS; TPC only.

TPC standalone resolution is of course much worse than the ITS, but gives the same position; i.e. the relative alignment is ok. The x resolution is for all momenta and track multiplicties; the actual beamspot (after unfolding) is slightly less than 200 micron.

Impact parameter distribution (DCA) of SPD tracklets to the found vertex. Sigma is about 190 micron for horizontal tracklets (all momenta and multipl.) (alignment error contribution < 15 micron). It is worse for vertical tracklets

(less statistics from cosmics available for alignment, to be done with collission events)




SPD tracklet to SPD vertex distance in (x,y) (cm)



Particle Identification










Decay Reconstruction








 M_{π^*p} (GeV/c²)














Jet1: uncalibrated E_T ~22 GeV, η = -2.1 Jet2: uncalibrated E_T ~11 GeV, η = 1.4


Online determination of the primary vertex and beam spot using the Level-2 trigger algorithms

High-Level Trigger running with > 150 chains











$K_s^0 \rightarrow \pi^+\pi^-$

2 opposite-sign tracks:

- p_T >500 MeV
- originating from common vertex
- \blacksquare impact parameter $d_0 > 4$ mm
- momentum sum along flight direction

Data and MC normalized to the same area







$\pi^0 \rightarrow \gamma \gamma$


- 2 photons with $E_T(\gamma)$ > 300 MeV
- \blacksquare E_T($\gamma \gamma$) > 900 MeV
- shower shapes compatible with photons

All combinations plotted.

No correction for upstream dead material (~ 2.5 X_0 at η =0) Data and MC normalised to the same area











Entries 14

12





Data conversion candidate

Electron candidates

O.5

ATLAS Preliminary

Non diffractive minimum bias MC: hadron fakes

Non diffractive minimum bias MC: electrons

O.4

Data


E_T Spec†rum

O.1


E_T (GeV)


Very good data-MC agreement for (soft!) electrons and hadrons


EM clusters E_T > 2.5 GeV matched to a track \rightarrow 47 candidates in 20000 minimum-bias events Data and MC normalised to the same area




■ Most electrons from γ -conversions









Energy flow in calorimeters ...





Uncalibrated clusters (topological clusters with noise suppression)




 $\frac{E(calorimeter)}{p(tracker)}$

for isolated tracks with $|\eta| < 0.8$ and 0.5 < p_T < 10 GeV (average ~ 0.8 GeV) Cluster energy at EM scale


Excellent agreement data-MC at such low energies indicates very good description of material in simulation and G4 shower modeling


... and missing transverse energy resolution



Energy resolution of the two components (METx, METy) of the missing E_{T} vector vs the total transverse energy in the calorimeters

- Measurement over full calorimeter coverage, $|\eta| < 5$, ~ 200000 cells
- Calculated using clusters at EM-scale
- Noise contribution (from random triggers): 0.5 GeV











Monday 23rd November






First Di-photon Distribution in CMS



Shown on Thursday 27th



- $M(\pi^0)$ is low in both data and MC
- Mostly due to the readout threshold (100 MeV/Crystal).
- Conversions: part of the energy is deposited upstream of ECAL.
- Event timing is consistent




Machinery in Place for Rapid Analysis

Sunday 6th Early Morning First: "Physics" Fill

4x4 bunches, $\Sigma \sim$ e10 protons Stable Beam Flag set for the first time


All CMS ON

Sunday 6th: 9am



Charged particle p_T spectrum produced a few hours after the first fill and compared with MC.


Monday 7th: 9am



 K^0 and Λ (η and ϕ have also been observed) Secondary vertex and track reconstruction in good shape, p/K hypotheses checked with Si dE/dx, magnetic field map is good



Jets



Anti- K_T algorithm with cone size R=0.7

	Jet 1	Jet 2
Corrected p _T (GeV)	24	26
η	0.3	2.0
ф	2.5	-0.7
EM Energy Fraction	0.5	0.6

UAM, March 2010




Calibration and Monitoring: Examples


Saturday 12th: "Physics" Fills (250k minbias events)

Reconstructed Primary Vertex Distributions

Beam scan yielded a factor 3 increase in rate at CMS!



CMS 2009 Preliminary




Run 124024

Taken on Sat 12th 14:57-17:06 Workflow for ECAL calibration Plot produced after a few hours


CMS

Performance of CMS Good agreement with MC Expectation






First Physics Distributions






Sunday 14th December @ 2.36 TeV



Ran from 4:17 to 5:49: Around 15k events taken




MultiJet Event at 2.36 TeV




4 PFlow Jets $E_T > 7$ GeV, p_T cut on tracks displayed > 0.4 GeV



Dimuon Event at 2.36 TeV




 $p_T(\mu_1) = 3.6 \text{ GeV}, \ p_T(\mu_2) = 2.6 \text{ GeV}, \ m(\mu\mu) = 3.04 \text{ GeV}$





pp interaction vertex as seen by VELO


(VELO is halfway to nominal operation position: each side is 15 mm away from the nominal position)




VELO + Outer Tracker + Silicon Tracker see K_S and Λ





Using all tracking power, especially VELO !!!






Tracking without VELO






RICH identifies kaons





Orange points – photon hits Continuous lines – expected distribution for each particle hypothesis (proton below threshold)



ECAL reconstructs π^0 signal





First data: 23 November 2009, No B-field

$$< m > = (133 \pm 3) \text{ MeV/}c^2$$

 $\sigma = (11 \pm 4) \text{ MeV/}c^2$

Now π^0 peak can be routinely monitored on-line:







 $M_{\gamma\gamma}$ (MeV/c²)


MIP identification using ECAL, HCAL & Muon








 E_{ECAL} (MeV)






First glance at the material distribution using γ conversions upstream the magnet: Tracker system and ECAL




 $M(e^+e^-)$ < 200 MeV/c² for any pair of the oppositely charged tracks




E/P


Z positions of the vertices reconstructed from 2 tracks with M(ee) < 200 MeV & E/p > 0.7 strongly peak at the location of the 2 stations of the Trigger Tracker: TT1 & TT2



Z, cm




Luminosity Ratios



Top quark

- Background to new physics searches must measure cross-section & properties in data
- Expected Tevatron statistics provide a benchmark:
 - Cross-section statistical precision will then be comparable to other uncertainties



~50 pb⁻¹@14 TeV would match full Tevatron sample

- lose ~factor 2 in cross-section dropping to 10 TeV
- lose ~another factor 2 dropping to 8 TeV

Below 8 TeV samples will be rather small, with a few tens of pb⁻¹


Catch up with Tevatron with $s^{1/2} = 8-10$ TeV and $\sim 200-100$ pb⁻¹ g.d.



Z

Z': Heavy partner of the Z (SSM)

- □ Very clean experimental signal: Z'→ℓℓ
- □ Tevatron 95% CL limit at m_Z =1 TeV




Needed luminosity for 95%CL exclusion

at
$$m_{Z'} = 1 \text{ TeV}$$
:

$$s^{1/2}$$
: 14 \rightarrow 10 \rightarrow 6 TeV


Lumi:
$$13 \rightarrow 30 \rightarrow 110 \text{ pb}^{-1}$$





SUSY, an example


- □ l+jets+missing-E_T channel
 - Not most sensitive, but will be usable before inclusive jets +missing-E_T analysis
- GeV in this model ($m_{\tilde{g}} = m_{\tilde{g}}$)
 - plot shows 3 masses above this
- We will be sensitive to a region overlapping with ultimate
 Tevatron reach
- □ Below E_{cm}≈8 TeV, the sensitivity collapses




 5σ discovery beyond current Tevatron limits is possible with $s^{1/2} = 8-10$ TeV and $\sim 30-15$ pb⁻¹ g.d.




Higgs 95% CL at LHC GPD, H→ weak bosons, indicative





Compare sensitivity to Tevatron with 8 fb⁻¹ (only $H\rightarrow WW\rightarrow lvlv$)




Massive loss of sensitivity below 6 TeV

To challenge Tevatron with $s^{1/2} = 7-10 \text{ TeV}$, we need ~300-200 pb⁻¹ g.d.

Physics reach for BR($B_s^0 \rightarrow \mu + \mu^-$)





as function of integrated luminosity (and comparison with Tevatron)



At $s^{1/2} = 8 \text{ TeV}$, need $\sim 0.3\text{-}0.5 \text{ fb}^{-1} \text{ g.d.}$ to improve on expected Tevatron limit

Collect \sim 3 fb⁻¹ for 3 σ observation of SM value


Heavy Ions: Flow at LHC



- one of the first and most anticipated answers from LHC
 - 2nd RHIC paper: Aug 24, 22k MB events, flow surprise (v₂)

LHC?

Hydrodynamics: modest rise (Depending on EoS, viscosity, speed of sound)



LHC:


the present and the (near) future




LHC Physics in 2010-2011

First beams: very early physics - rediscover SM physics

Detector synchronization, in-situ alignment and calibration



10 pb⁻¹: Standard Model processes measure jet and lepton rates, observe W, Z bosons first look at possible extraordinary signatures...



30 pb⁻¹

Measure Standard Model Processes (at 10TeV need ~ 30pb⁻¹):

 $\sim 10^4 \text{ Z} \rightarrow \text{e+e-}$ (golden Z's for detector studies (1%))

 $\sim 10^5 \, \mathrm{W} \rightarrow \mathrm{ev}$

~ 10^3 ttbar (measure σ to 10%)

Background for new physics
Need to understand very well

Initial Higgs searches and searches for physics beyond the SM

 $> 200 \text{ pb}^{-1}$

Entering Higgs discovery era and explore large part of SUSY and new resonances at ~ few TeV




Beam Energy; Chamonix

- Simulations for safe current used pessimistic input parameters (RRR.....) but have no safety margins
- For 2010, 3.5 TeV is safe
 - Measure the RRR (asap) to confirm the safety margin for 3.5TeV/beam
- Without repairing the copper stabilizers, 5 TeV is risky

Decision from Management/detectors following Chamonix

 Run at 3.5 TeV/beam up to a predefined integrated luminosity with a date limit. Then consolidate the whole machine for 7TeV/beam.

Time lines (Very Preliminary)




Next year we talk about the far future!

Luminosity

$$L = \frac{N^2 k_b f}{4\pi\sigma_x \sigma_y} F = \frac{N^2 k_b f \gamma}{4\pi\varepsilon_n \beta^*} F$$

- Nearly all the parameters are variable (and not independent)
 - Number of particles per bunch
 - Number of bunches per beam
 - Relativistic factor (E/m₀)
 - Normalised emittance
 - Beta function at the IP
 - Crossing angle factor
 - Full crossing angle
 - Bunch length
 - Transverse beam size at the IP σ^*





$$F = 1/\sqrt{1 + \left(\frac{\theta_c \sigma_z}{2\sigma^*}\right)^2}$$


 ε_n

F

 σ_{z}

Roger Bailey

LHC performance drivers/limiters



β * and F in 2010


- Lower energy means bigger bean $\varepsilon_n = \varepsilon \gamma$
- $\sigma = \sqrt{\varepsilon \beta}$

At

max


- Less aperture margin
- Higher β *
- > 150 bunches requires crossing angle (beambeam)
 - Requires more aperture
 - Higher β *
- Targets for 3.5TeV
 - 2/2.5 m without/with crossing angle in 2010
 - 2m with crossing angle in 2011

Interaction Region - F



With > 150 bunches per beam, need a crossing angle to avoid parasitic

"Intensity limits" Collimation (2010)



Collimator "limit" around 6 10¹³ protons per beam at 3.5TeV with "intermediate" settings (about 20% nominal intensity)

33.6 MJ stored beam energy


Soft limit, not yet well defined, 0.2%/s loss rate totally arbitrary (8 minute lifetime)

Strategy for Increasing the Beam Intensity

- The magic number for 2010/11 is 1 fb⁻¹. To achieve this, the LHC must run flat out at 2x10³² cm⁻²s⁻¹ in 2011,
 - Correspond to 8e10 ppb, 700 bunches, with a stored energy of 35 MJ (with β *=2 m and nominal emittance).

Progression (2)

□ After 30 weeks: ~1E32 cm-2s-1, 12 MJ.




2011

3.5 TeV: run flat out at ~100 pb⁻¹ per month

	No. bunche s	ppb	Total Intensity	Beam Stored Energ y (MJ)	beta*	Peak Lumi	Int Lumi per month
50 ns	432	7 e10	3 e13	17	2	1.3 e32	~85
Pushing intensity limit	720	7 e10	5.1 e13	28.2	2	2.2 e32	~140
Pushing bunch current limit	432	11 e10	4.8 e13	26.6	2	3.3 e32	~209

With these parameters we should be able to deliver 1 fb⁻¹



In summary

- We are finally entering the LHC era
- Ready to rediscover all the Standard Model
- ..and use it for "calibration"
- An entire new space of parameters opens up for the discovery of the "known unknown"...



In summary

...and there might be welcomed surprises

...without forgetting that....

...the only place in which success comes before work is in the dictionary

